ROYALTY CALCULATION

Name of Work : Comminity Property Maintenance (Including Building and Parks)in Ward No 13 Mallasandra, Shettyhalli sub Division

Plain Cement Concrete 1:3:6			
Description	Qty in Cum	Constant	Total Qty
Sand	17.41	0.465	8.10
Jelly	17.41	0.892	15.53
SSM 1:6			
Sand	20.51	0.30	6.15
Jelly	20.51	1.05	21.54
Sand	10.62	0.018	0.19
Jelly	10.62		
M-25			
Sand	44.58	0.47	20.95
Jelly	44.58	0.70	31.21
MMM			
Sand	16.61	0.26	4.32
Jelly	16.61	485	
11-10 CM Wall			
Sand	9	0.26	2.34
Jelly	9	66.8	
18MM Plaster			
Sand	191.45	0.018	3.45
Jelly	191.45		

Scanned by CamScanner

Name of Work : Comminity Property Maintenance (Including Building and Parks)in Ward No 13 Mallasandra, Shettyhalli sub Division

12MM Plaster			
Sand	16.36	0.012	0.20
Jelly	16.36		
Tiles			
Sand	370.69	0.020	7.41
Jelly	370.69		

Sl	Items	Qty	Rate	Amount
1	Sand	46.95	138.00	6480.00
2	Jelly	68.27	126.00	8602.00
			Total	15082.00

Asst.Engineer

Ward-13

Asst.Executive Engineer
Shettyhalli Sub Division

Scanned by CamScanner